

Recent activities at Jefferson Laboratory - Progress of the new SRF facilities and CEBAF 12GeV upgrade cavity results

Dr. Ari D. Palczewski – SRF Research & Development Scientist

Part 1 New TEDF/SRF Development Facilities

- TEDF project buildings
- Design goals
- New facility foot print
- Workflow improvements
- New clean and chemical room design

Part 2 – CEBAF 12 GeV SRF Upgrade Cavity Testing Results

- CEBAF overview
- 12GeV upgrade cavity design
- Cavity processing
- Full VTA cavity tests results with FE

Thomas Jefferson National Accelerator Facility

Newport News, Virginia



39°51'28.00" N 96°07'33.60" W



Jefferson National Laboratory (JLAB)

Department of Energy (DOE) single function Laboratory – Nuclear physics

- One of 17 national labs in the United States
- ~700 employee's (~1000 during construction/12GeV)
- ~1300 visiting scientist a year
- CEBAF (continual electron beam accelerator facility) – nuclear physics 5 pass racetrack dual LINAC
- Free electron laser – 14.2 kilowatts of cw light at 1.6 microns (100W @ 363nm)
- Full functional Superconducting Radio Frequency(SRF) cavity processing facility



Jefferson Lab Technology and Engineering Development Facility Project (TEDF)

A DOE Science
Laboratory
Infrastructure
modernization
project

Provides the first
2nd-generation SRF
facility in the world



TED building 2012

New SRF lab TLA (Addition) 2012

Renovated SRF Test Lab (TL) 2013

TED extension/addition building


Replaces temporary building and rental offices

- Temporary home of SRF during test lab renovation (through summer 2013)
- New home for Engineering staff
- New home for some Cryogenic staff
- New home for some accelerator support staff
- New home for electronics assembly and design




TEDF Project- SRF TLA/Addition


- Department of Energy – “Science Laboratory Infrastructure” Project
- Investment in facilities for:
 - Improved energy efficiency
 - Improved safety code compliance – new building
 - Improved human work environment- lighting and ergonomics
 - **Increased build out capacity – future projects**
 - Improved technical quality of facilities for future work
 - Improved work-flow efficiency




SRF Work Centers in Test Lab – OLD design



Test Lab 2nd Floor



SRF Work Centers in New Test Lab



SRF Facilities in TEDF Project

Advanced Conceptual Design

Chemistry, cavity treatments, and support areas

R&D


Cavity and cryomodule cryo/RF testing

Cleanroom

Cryomodule assembly

Fabrication

New



Jefferson Lab
Scale: 1/8" = 1'-0" 03.26.09

Renovation and Addition - First Floor

Build

SRF Facilities in TEDF Project

Advanced Conceptual Design

Chemistry, cavity treatments, and support areas

R&D


Cavity and cryomodule cryo/RF testing

Cleanroom

Cryomodule assembly

Fabrication

New



Jefferson Lab
Scale: 1/8" = 1'-0" 03/26/09

Renovation and Addition - First Floor

Build

Chemistry and Ultra pure water

Upgraded chemical management and waste treatment systems

- Semi-automatic bulk chemical delivery systems to tools
- Upgrade chemical wet stations
- Use of double containment and valve manifold boxes for safety
- Automated neutralization system



Upgraded ultrapure water system

- Specified to meet ASTM Type E-1.1 (18.2 MΩ)
- Centralized Hot UPW system

Process Support Area
“dirty”



Clean Room

Process Tool



Centralized Bulk Chemistry neutralization

- Extension building dedicated for neutralization only
- Single building for R&D and production
- Fully automated neutralization and monitoring



Back of chemical room

SRF Facilities in TEDF Project

Advanced Conceptual Design

Chemistry, cavity treatments, and support areas

R&D

Cavity and cryomodule cryo/RF testing

Cleanroom

Cryomodule assembly


Fabrication

New

Jefferson Lab
Scale: 1/8" = 1'-0" 03.20.09

Renovation and Addition - First Floor



Built



New clean room facilities

Upgraded clean room space to ISO-4 (all class 10 assembly)

- 100% HEPA coverage, RMF, laminar flow with return plenums
- Bay/Chase concept
- Dedicated Drying & Assembly chambers
- Modular wall systems
- Cavity string air lock



SRF Facilities in TEDF Project

Advanced Conceptual Design

Chemistry, cavity treatments, and support areas

R&D


Cavity and cryomodule cryo/RF testing

Cleanroom

Cryomodule assembly

Fabrication

New




Jefferson Lab
Scale: 1/8" = 1'-0" 03.26.09

Renovation and Addition - First Floor

Build

Expanded cryo-module assembly area

- Upgraded cryomodule assembly space
 - Additional rails to allow for simultaneous C50, C100, and R&D assemblies



Expect great thing in 2013 after construction is complete



Moving into cryomodule area



New Offices under construction




Moving into assembly area

Part 1 questions?


Part 2 - CEBAF 12 GeV Upgrade

10 New cryo-modules - 8 cavities each
 ≥ 108 MV avg.
300 W @ 2.07K



Cavity: 0.7 m, "Low loss" cell shape, 1.497 GHz
8 cavities/cryomodule

12 GeV Upgrade cavity
7 cell low loss fabricated by Research Instruments (RI -Germany)



Spec - 19.2MV/m below 29 watts ($Q=7.2 \cdot 10^9$)


12 GeV Upgrade Cavities

- **Production process** – press for reliable efficiency
 - **160 μm BCP** etched and pre-tuned **by vendor**
 - Receipt inspection – mechanical and RF
 - Bake: **600 C, 10 hrs**
 - EP: **30 μm , @20°C** regulated by external water spray/degrease
 - **Tune**
 - Helium vessel welding
 - Flange lapping/degrease
 - **HPR**
 - Partial assembly
 - **HPR** >> dry in Class 10 cleanroom
 - Final assembly, leak check
 - Bake: **120° C, 24 hrs**
 - **Vertical test @ 2.07 K**
 - **HPR** >> dry in Class 10
 - String assembly


A. Reilly et al., *Preparation and Testing of the SRF Cavities for the CEBAF 12 GeV Upgrade*, TUPO061 **SRF 2011 Conference**.

CEBAF 12 GeV project cavities

12 GeV C100 Cavity Final E_{max} Acceptance Test




Full cavity statistics all VTA cycles



Cavities which did not meet spec - defects

c100-26 cell 5

Only 1 cavity was
quench limited below
spec by original
manufacturing defect



Cat eye

c100-8 iris 2-6

Accidental Cavity scratch
from HPR




Post re-EP



Field Emission Statistics – vertical qualification test

- Field emission monitored above the top plate of the Dewar within the shield lid. – 6 feet above and 3 feet off axis
- Data take every 0.3 seconds - Canberra IP-100 area monitor
- Continually monitored and data logged
- Our radiation is monitored in mRad/hr (i.e. mRad/hr=10 μ Sv/hr)
- VTA operator compiles data after each test and places individual cavity results into centralized database

C100 Cavity Initial FE Onset (Final Test)




J. Leung

1mR = 10 μ Sv

Average = 190 μ Sv/hr in VTA

C100 & R100 Cavity FE @ 20 MV/m (Final Test)





12GeV - Cryomodule data

- Modules 1 and 2 installed in 2011 both have worked at spec of (108.2MV) with beam
- Modules 3 and 4 are complete and in the tunnel
- Modules 5 and 6 are complete and awaiting test
- Modules 7-10 are at various stages of completion, but all strings are fully assembled under vacuum
- Final instillation slated for 2013 with full operations by end of 2014 – 16 month shutdown just started May 2012
- Field emission test data for Cryomodule expected – early 2014



Other SRF Projects

- FRIB:
 - Committed to do processing of all half-wave cavities
 - In discussion full cryomodule design, assembly, and testing
- APS - construct crab cavity prototype
- Project X - designed, constructed and tested new 650 MHz cavity shape to minimize multipacting
- Next Generation Light Source - collaboration w/LBNL, FNAL, SLAC
- ILC - leading gradient improvement effort - CBP/VEP/FE mapping
- BES inverse compton scattering source – developing technology
- European Spallation Source – in negotiations re spoke cavity R&D




Special Thanks

- Entire Jefferson SRF Institute technical and production staff including Scientist and VTA operators for individual FE statistics
- Jonny Jeung for FE database analysis
- Charlie Reece and Tony Reilly for TEDF slides



Jefferson Science Associates, LLC under U.S. DOE
Contract No. DE-AC05-06OR23177

12 GeV Upgrade Cryomodule

First cavity string @ completion





Installation of super-insulation on upgrade cryomodule



First cryomodule in CEBAF tunnel

Improved Technical Quality of Facilities for Future Work

- **Upgraded clean room space to ISO-4 (all class 10)**
 - 100% HEPA coverage, RMF, laminar flow with return plenums
 - Bay/Chase concept
 - Dedicated Drying & Assembly chambers
 - Modular wall systems
 - Cavity string air lock
- **Upgraded chemical management and waste treatment systems**
 - Semi-automatic bulk chemical delivery systems to tools
 - Upgrade chemical wet stations
 - Use of double containment and valve manifold boxes for safety
 - Automated neutralization system
- **Upgraded ultrapure water system**
 - Specified to meet ASTM Type E-1.1 (18.2 MΩ)
 - Centralized Hot UPW system
- **Upgraded cryomodule assembly space**
 - Additional rails to allow for simultaneous C50, C100, and R&D assemblies



TEDF SRF Infrastructure Design

30,000 sq foot – all new

RF structure development

Cavity fabrication (presses, EBW...)

QC/ Inspection


Integrated cleanroom suite

- Production chemroom
- R&D chemroom
- Flexible ISO 4 assembly areas
- Clean material analysis lab


New materials R&D lab

Dedicated CEBAF-support CM assembly lines

Expansion assembly space for other DOE project support



12 GeV vertical test - all upgrade cavities 80 needed for project



86 cavities

Improved Work-Flow Efficiency – next 2 slides

- Improved work flow of SRF work centers by consolidating to Test Lab Addition (TLA)
 - All work centers placed on first floor level
 - SRF machine shop, presses, tech shop, and electron beam welder consolidated in one area
 - Brazing and vacuum furnaces moved to one room
 - Parts clean & etch, R&D chemistry co-located to east end of TLA with improved integration with clean room
 - Consolidated R&D labs
 - Vertical attach clean room isolated from main ISO-4 clean room used for cavity processing and assembly via an air lock
 - Longer dedicated cryomodule assembly rail systems to enable simultaneous activities