

# Recent activities at Jefferson Laboratory - Progress of the new SRF facilities and CEBAF 12GeV upgrade cavity results

Dr. Ari D. Palczewski – SRF Research & Development Scientist

# Part 1 New TEDF/SRF Development Facilities

- TEDF project buildings
- Design goals
- New facility foot print
- Workflow improvements
- New clean and chemical room design

## Part 2 – CEBAF 12 GeV SRF Upgrade Cavity Testing Results

- CEBAF overview
- 12GeV upgrade cavity design
- Cavity processing
- Full VTA cavity tests results with FE

# Thomas Jefferson National Accelerator Facility

Newport News, Virginia



39°51'28.00" N 96°07'33.60" W



SRF Research and accelerator production facilities

# Jefferson National Laboratory (JLAB)

Department of Energy (DOE) single function Laboratory – Nuclear physics

- One of 17 national labs in the United States
- ~700 employee's (~1000 during construction/12GeV)
- ~1300 visiting scientist a year
- CEBAF (continual electron beam accelerator facility) – nuclear physics 5 pass racetrack dual LINAC
- Free electron laser – 14.2 kilowatts of cw light at 1.6 microns (100W @ 363nm)
- Full functional Superconducting Radio Frequency(SRF) cavity processing facility



# Jefferson Lab Technology and Engineering Development Facility Project (TEDF)

A DOE Science  
Laboratory  
Infrastructure  
modernization  
project

Provides the first  
2<sup>nd</sup>-generation SRF  
facility in the world



TED building 2012

New SRF lab TLA (Addition) 2012

Renovated SRF Test Lab (TL) 2013

# TED extension/addition building

Replaces temporary building and rental offices

- Temporary home of SRF during test lab renovation (through summer 2013)
- New home for Engineering staff
- New home for some Cryogenic staff
- New home for some accelerator support staff
- New home for electronics assembly and design




# TEDF Project- SRF TLA/Addition

- Department of Energy – “Science Laboratory Infrastructure” Project
- Investment in facilities for:
  - Improved energy efficiency
  - Improved safety code compliance – new building
  - Improved human work environment- lighting and ergonomics
  - **Increased build out capacity – future projects**
  - Improved technical quality of facilities for future work
  - Improved work-flow efficiency




# SRF Work Centers in Test Lab – OLD design




**Test Lab 1<sup>st</sup> Floor**

**Test Lab 2<sup>nd</sup> Floor**



# SRF Work Centers in New Test Lab



# SRF Facilities in TEDF Project

Advanced Conceptual Design

Chemistry, cavity  
treatments, and  
support areas

R&D

Cavity and  
cryomodule  
cryo/RF testing

Cleanroom

Cryomodule  
assembly


Fabrication

New

Jefferson Lab  
Scale: 1/8" = 1'-0" 03.26.09


Renovation and Addition - First Floor

Build



# SRF Facilities in TEDF Project

Advanced Conceptual Design



# Chemistry and Ultra pure water

## Upgraded chemical management and waste treatment systems

- Semi-automatic bulk chemical delivery systems to tools
- Upgrade chemical wet stations
- Use of double containment and valve manifold boxes for safety
- Automated neutralization system


## Upgraded ultrapure water system

- Specified to meet ASTM Type E-1.1 (18.2 MΩ)
- Centralized Hot UPW system

Process  
Support Area  
“dirty”


Clean  
Room

Process  
Tool



# Centralized Bulk Chemistry neutralization

- Extension building dedicated for neutralization only
- Single building for R&D and production
- Fully automated neutralization and monitoring



Back of chemical room

## Advanced Conceptual Design

# Chemistry, cavity treatments, and support areas

R&amp;D

# Cavity and cryomodule cryo/RF testing

# Cleanroom

# Cryomodule assembly

## Fabrication

New

Jefferson Lab  
Scale: 1/8" = 1'-0" 03.26.09



## Renovation and Addition - First Floor

## Build

# New clean Room facilities

## Upgraded clean room space to ISO-4 (all class 10 assembly)

- 100% HEPA coverage, RMF, laminar flow with return plenums
- Bay/Chase concept
- Dedicated Drying & Assembly chambers
- Modular wall systems
- Cavity string air lock



## Advanced Conceptual Design

# Chemistry, cavity treatments, and support areas

R&amp;D

# Cavity and cryomodule cryo/RF testing

# Cleanroom

# Cryomodule assembly

## Fabrication

New

Jefferson Lab  
Scale: 1/8" = 1'-0" 03.26.09

## Renovation and Addition - First Floor


## Build



- Additional rails to allow for simultaneous C50, C100, and R&D assemblies



# Expect great thing in 2013 after construction is complete




# Part 1 questions?

# Part 2 - CEBAF 12 GeV Upgrade

10 New cryo-modules - 8 cavities each


$\geq 108$  MV avg.

300 W @ 2.07K



Cavity: 0.7 m, "Low loss" cell shape, 1.497 GHz  
8 cavities/cryomodule

12 GeV Upgrade cavity  
7 cell low loss fabricated by Research Instruments (RI -Germany)



Spec - 19.2MV/m below 29 watts ( $Q=7.2 \cdot 10^9$ )


# 12 GeV Upgrade Cavities

- **Production process** – press for reliable efficiency
  - **160  $\mu\text{m}$  BCP** etched and pre-tuned **by vendor**
  - Receipt inspection – mechanical and RF
  - Bake: **600 C, 10 hrs**
  - EP: **30  $\mu\text{m}$ , @20°C** regulated by external water spray/degrease
  - **Tune**
  - Helium vessel welding
  - Flange lapping/degrease
  - **HPR**
  - Partial assembly
  - **HPR** >> dry in Class 10 cleanroom
  - Final assembly, leak check
  - Bake: **120° C, 24 hrs**
  - **Vertical test @ 2.07 K**
  - **HPR** >> dry in Class 10
  - String assembly


A. Reilly et al., *Preparation and Testing of the SRF Cavities for the CEBAF 12 GeV Upgrade*, TUPO061 **SRF 2011 Conference**.

# CEBAF 12 GeV project cavities

## 12 GeV C100 Cavity Final $E_{max}$ Acceptance Test




# Full cavity statistics all VTA cycles



# Cavities which did not meet spec - defects

## c100-26 cell 5

Only 1 cavity was  
quench limited below  
spec by original  
manufacturing defect



Cat eye

## c100-8 iris 2-6

Accidental Cavity scratch  
from HPR




Post re-EP



# Field Emission Statistics – vertical qualification test

- Field emission monitored above the top plate of the Dewar within the shield lid. – 6 feet above and 3 feet off axis
- Data take every 0.3 seconds - Canberra IP-100 area monitor
- Continually monitored and data logged
- Our radiation is monitored in mRad/hr (i.e.  $\text{mRad/hr} = 10\mu\text{Sv/hr}$ )
- VTA operator compiles data after each test and places individual cavity results into centralized database

# C100 Cavity Initial FE Onset (Final Test)




J. Leung

1mR = 10 $\mu$ Sv

Average = 190  $\mu$ Sv/hr in VTA

C100 & R100 Cavity FE @ 20 MV/m (Final Test)





# 12GeV - Cryomodule data

- Modules 1 and 2 installed in 2011 both have worked at spec of (108.2MV) with beam
- Modules 3 and 4 are complete and in the tunnel
- Modules 5 and 6 are complete and awaiting test
- Modules 7-10 are at various stages of completion, but all strings are fully assembled under vacuum
- Final instillation slated for 2013 with full operations by end of 2014 – 16 month shutdown just started May 2012
- Field emission test data for Cryomodule expected – early 2014



# Other SRF Projects

- FRIB:
  - Committed to do processing of all half-wave cavities
  - In discussion full cryomodule design, assembly, and testing
- APS - construct crab cavity prototype
- Project X - designed, constructed and tested new 650 MHz cavity shape to minimize multipacting
- Next Generation Light Source - collaboration w/LBNL, FNAL, SLAC
- ILC - leading gradient improvement effort - CBP/VEP/FE mapping
- BES inverse compton scattering source – developing technology
- European Spallation Source – in negotiations re spoke cavity R&D



# Special Thanks

- Entire Jefferson SRF Institute technical and production staff including Scientist and VTA operators for individual FE statistics
- Jonny Jeung for FE database analysis
- Charlie Reece and Tony Reilly for TEDF slides


Jefferson Science Associates, LLC under U.S. DOE  
Contract No. DE-AC05-06OR23177

# 12 GeV Upgrade Cryomodule

First cavity string @ completion





Installation of super-insulation on upgrade cryomodule



First cryomodule in CEBAF tunnel

# Improved Technical Quality of Facilities for Future Work

- Upgraded clean room space to ISO-4 (all class 10)
  - 100% HEPA coverage, RMF, laminar flow with return plenums
  - Bay/Chase concept
  - Dedicated Drying & Assembly chambers
  - Modular wall systems
  - Cavity string air lock
- Upgraded chemical management and waste treatment systems
  - Semi-automatic bulk chemical delivery systems to tools
  - Upgrade chemical wet stations
  - Use of double containment and valve manifold boxes for safety
  - Automated neutralization system
- Upgraded ultrapure water system
  - Specified to meet ASTM Type E-1.1 (18.2 MΩ)
  - Centralized Hot UPW system
- Upgraded cryomodule assembly space
  - Additional rails to allow for simultaneous C50, C100, and R&D assemblies



# TEDF SRF Infrastructure Design

## 30,000 sq foot – all new

# RF structure development

## Cavity fabrication (presses, EBW...)

## QC/ Inspection


## Integrated cleanroom suite

- Production chemroom
- R&D chemroom
- Flexible ISO 4 assembly areas
- Clean material analysis lab


## New materials R&D lab

## Dedicated CEBAF-support CM assembly lines

Expansion assembly space for  
other DOE project support



# 12 GeV vertical test - all upgrade cavities 80 needed for project



86 cavities

# Improved Work-Flow Efficiency – next 2 slides

- Improved work flow of SRF work centers by consolidating to Test Lab Addition (TLA)
  - All work centers placed on first floor level
  - SRF machine shop, presses, tech shop, and electron beam welder consolidated in one area
  - Brazing and vacuum furnaces moved to one room
  - Parts clean & etch, R&D chemistry co-located to east end of TLA with improved integration with clean room
  - Consolidated R&D labs
  - Vertical attach clean room isolated from main ISO-4 clean room used for cavity processing and assembly via an air lock
  - Longer dedicated cryomodule assembly rail systems to enable simultaneous activities